



# ATTUKAL BHAGAVATHY TEMPLE TRUST

P.B.NO. 5805

ATTUKAL, THIRUVANANTHAPURAM-695009

Ref No S2/1186/2024/ABTT/ 1628

Date : 17/05/2024

## Quotation Notice

Quotations are invited for the supply and installation of CCTV Cameras at Devi Auditorium. The quotation addressed to the Secretary, Attukal Bhagavathy Temple Trust should reach this office on or before **23/05/2024 - 3.00 pm**. The quotations will be opened at 4.00 pm on the same day.

The item "**Supply and installation of CCTV Camera- Devi Auditorium**" should be noted on the envelope. The rate quoted for the CCTV Camera should be inclusive of all Taxes and installation charges.

### SPECIFICATION FOR CCTV CAMERA WITH ACCESSORIES.

No.	Item	Qty
1	CP PLUS - 5 Mega pixel IP Metal Body Bullet camera 30 Meter & 4x4 PVC Camera Box with Installation	11 Nos.
2	CP PLUS - 5 Mega pixel IP Metal Body Dome Camera 30 Meter & 4x4 PVC Camera Box with Installation	11 Nos.
3	Single Mode SFP Module 1Gbps - Compatible	2 Nos.
4	32 Channel Rack Mountable NVR - 4K - CP-PLUS Bandwidth more than 300 Mbps - with Installation	1 Nos.
5	CP PLUS 8 + 2 - 1Gbps POE SWITCH (with SFP Module support) - with installation	3 Nos.
6	10TB Surveillance Hard Disk (WD / Seagate) - with installation	1Nos.
7	Supply and laying along with accessories Cat 6 UTP Cable. Supports ultrahigh speed data networks such as Gigabit Ethernet (1000 e-T and 1000 Base TX and beyond)	500 Meter (Approximate)

8	Supply and fixing of following size of medium class ISI marked PVC conduit along with accessories in surface or recess including cutting the wall making good the same in case of recessed conduit as required (a) 20 MM (b) 25 MM	500 Meter (Approximate)
9	Optical fiber cable (6 core) with Installation Charge in PVC 20mm with conduit & accessories	80 Meter (Approximate)
10	Supply and installation of 650/1100 grade FRLS PVC insulated standard single-core copper conductor cables, complying with ISI 694 part 1990, in the existing surface or recessed conduit as necessary, including the provision of required connections of appropriate size. 1sq.mm 3 core	120 Meter (Approximate)
11	Supply and installation of medium-class PVC conduit in the following sizes, along with accessories, on the surface or recessed as needed, including wall cutting and making good the same in the case of recessed conduit as required. (a) 20 MM (b) 25 MM	120 Meter (Approximate)
12	42" VU HD TV - With installation	1 Nos.
13	22" LED Monitor (Acer / HP / Lenovo) - With installation	1 Nos.
14	VGA CABLE – With Installation	5 Meter
15	HDMI CABLE – With Installation	20 Meter
16	6U Rack (D-Link/NETRACK) – with PDU and cooling Fan (ISI/ISO certified) with installation	1 Nos.
17	POE BOX 12" - with installation	2 Nos.
18	Supply and fixing modular socket & Switch – 5A On the modular plate and PVC Box including Connection. (ISI marked)	7 Nos.
19	Dlink RJ 45 Connector	100 Nos
20	Configuration Charges including Rack fixing, dressing and labelling	

**Terms and Conditions.**

- a. The equipment supplied should be under on-site warranty for a period of 3 years.
- b. No escalation of rate will be considered after submission of the Quotation.
- c. For Camera & NVR Manufacture Authorization Form from OEM is mandatory
- d. The vendor should be able to complete the supply, installation, testing, Commissioning of 22 nos. IP Cameras with NVR Systems within 15 days from the date of work order.
- e. The retention amount of 5% of the work value will be kept for 36 months from the date of completion of the work and the retention amount will be refunded to the bidder, after deducting any sum due from the bidder on any account under this contract. No interest will be given on retention money.
- f. Payment will be made based on actual measurements.

**Yours faithfully**

**SECRETARY**

